

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-30105-00-01
Spot: SWNWSESE Sec/Twnshp/Rge: 36-27S-13W
846 feet from S Section Line, 1262 feet from E Section Line
Lease Name: GIBBONS HESS Well #: 1
County: PRATT Total Vertical Depth: 4338 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4180		
COND	13	185		
PROD	4.5	4338	0	WITH 125 SX CMT
RBP		4100		WITH 10 SX CMT ON TOP
SURF	8.625	695		WITH 400 SX CMT

Well Type: EOR UIC Docket No: E26761.6 Date/Time to Plug: 07/29/2014 12:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 07/29/2014 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

****RBP HUNG UP IN COLLAPSED CASING AT 4180** SPOT 10 SX CMT ON TOP OF RBP AT 4100'. PERFORATE AT 725'. RUN TBG IN TO 725 & PACK OFF. CIRCULATE CMT TO SURFACE IN 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS WITH 215 SX CMT**

Perfs:

Top	Bot	Thru	Comments
4312	4320		

Received
KANSAS CORPORATION COMMISSION

Remarks: **COMPLIANCE ISSUE: FAILED MIT** CMT BY BASIC ENERGY SERVICES.

AUG 13 2014

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

AUG - 8 2014

KCC DODGE CITY

Signed

cc: UTC
8-18-14 ckm

(TECHNICIAN)