

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20376-00-00
Spot: SESE Sec/Twnshp/Rge: 20-11S-41W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: HILL Well #: 2-20
County: WALLACE Total Vertical Depth: 1256 feet

Operator License No.: 33953
Op Name: RAVEN RESOURCES LLC
Address: PO BOX 721880
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1242		115 SX
SURF	7	245		68 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/15/2014 2:00 PM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: DAVID STEWART Company: RAVEN RESOURCES Phone: (405) 773-7340

Proposed Plugging Method: 7" surface pipe set at 245' w/68 sx cement. 4.5" production casing set at 1242' w/115 sx cement. TD 1256'. PBTD 1200'.
Perforation interval is unknown.
Ordered 140 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2014 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 1170' and pumped 75 sx cement w/200 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 10 sx cement. Pressured to 300 psi. Connected to 7" surface casing and pumped 10 sx cement. Pressured to 300 psi.

GPS: 39.07706N -101.88911W

Perfs:

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 46606

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 28 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Darrel Dipman
8-18-14 ckm (TECHNICIAN)

CM

JUL 18 2014