

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20997-00-00
Spot: NENWNW Sec/Twnshp/Rge: 24-9S-23W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: NINEMIRE Well #: 2
County: GRAHAM Total Vertical Depth: 3914 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3911 | | 200 SX |
| SURF | 8.625 | 166 | | 140 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2014 12:00 PM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: RON'S OIL OPERATIONS Company: POE Phone: (785) 421-2315

Proposed Plugging Method: Perforations at 3836' - 3842'
Shot perforation at 1200', 1990' and 2600'
Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2014 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3350' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2670' and pumped 125 sx cement w/150 # hulls. Pulled tubing to 1460' and pumped 155 sx cement w/150 # hulls. Good circulation of cement. Pulled tubing out. Topped off w/25 sx cement full. Tied on to backside and squeezed w/50 sx cement.
GPS: 39.26192 -099.84374

Perfs:

Remarks: GLOBAL CEMENT TICKET # 1408

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION
AUG 14 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed *Marvin Mills*
8-14-18 ckm (TECHNICIAN) CM

AUG 12 2014