

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21217-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 24-9S-23W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: NINEMIRE Well #: 4-24  
County: GRAHAM Total Vertical Depth: 3978 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC  
Address: 1889 200TH AVE  
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3973		125 SX
SURF	8.625	167		145 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2014 11:00 AM  
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC  
Proposal Rcvd. from: RONALD NICKELSON Company: POE Phone: (785) 421-2315

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Perforations at 3877' - 3882' and 3917' - 3922'.  
Shot perforations at 1200', 1990' and 2600'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/08/2014 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3750' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2580' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1100' and pumped 190 sx cement. Good circulation of cement. Pulled tubing out. Topped off with 40 sx cement full. Tied on to backside and squeezed w/60 sx cement.

GPS: 39.26018 -099.83684

Perfs:

Remarks: GLOBAL CEMENT CO TICKET # 1409

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION

AUG 14 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

8-18-14 CKM

(TECHNICIAN)

CA

AUG 12 2014