

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-20777-00-00
Spot: SESENESE Sec/Twnshp/Rge: 5-25S-13E
1452 feet from S Section Line, 317 feet from E Section Line
Lease Name: HOLLISTER Well #: 14
County: GREENWOOD Total Vertical Depth: 1525 feet

Operator License No.: 5684
Op Name: SAGE, LARRY GEORGE
Address: PO BOX 12
VIRGIL, KS 66870

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2014 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 1525' 50' cement plug @ 600' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2014 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

connect to 4 1/2" casing pumped 15 sx cement w/hulls, pumped 10 sxs cement @ 600',
pumped 22 sx cement @ 300' to surface, shut in well @ 1200 lbs. , gel spacers between cement
plugs.

Perfs:

RECEIVED
AUG 11 2014
KCC Chanute Dist. #3

mtt

Received
KANSAS CORPORATION COMMISSION

AUG 14 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed *Mike DeGlen*
8-18-14 CKM (TECHNICIAN)

Hurricane Services, Inc.
 3613 A.Y. Road
 Madison, KS 66860
 Office # 620-437-2661
 Brad Cell # 620-437-6765



HURRICANE SERVICES INC
 OILFIELD SERVICES
 MADISON, KANSAS

Ticket Number 100509
 Location Madison
 Foreman Brad Butler

Copy for Mike Heggan API#15-073-20777

Cement Service ticket

Date	Customer #	Well Name & Number	Sec./Township/Range	County
7-28-14		Holester # 14	5-2S-13	Greenwood
Customer		Mailing Address	City	State Zip
George Sage				

Job Type:	Plug to Abandon			Truck #	Driver
Hole Size:	Casing Size: 4 1/2"	Displacement:	201	Jerry	
Hole Depth:	Casing Weight:	Displacement PSI:	202	Bryan	
Bridge Plug:	Tubing:	Cement Left in Casing:	106	David	
Packer:	PBTD:	Pegs @ 1422 to 1423"			

Quantity Or Units	Description of Services or Product	Pump charge	
25	Mileage	\$3.25/Mile	790.00
			81.25
47 SACKS	60/40 Pozmix Cement	12.00	564.00
160 lbs.	Gel 4%	.30	48.00
80 lbs.	CaCl ₂ 2%	.75	60.00
200 lbs.	Gel > Spacer between plugs	.30	60.00
3 Hrs.	Water Truck	84.00	252.00
Received KANSAS CORPORATION COMMISSION			
Tons	Bulk Truck > minimum charge	AUG 14 2014	300.00
CONSERVATION DIVISION WICHITA, KS			
	Plugs		
		Subtotal	2155.25
		Sales Tax 7.15%	52.34
		Estimated Total	2207.59

Remarks: Rig up to 4 1/2" casing, Pumped into well @ 2 1/2 BPM with 500 PSI. Premix CaCl₂ in mixing water. Mixed 15 sacks cement w/ CaCl₂ and Hulls, followed with 10 Bl. Gel Spacer, Mix 10 sacks cement w/ CaCl₂, followed with 2 1/2 Bl. Water Spacer, mixed 22 sacks cement for top plug.

Note: Pumping into formation with 500 PSI, when cement hit Perfs. Pressure @ 900 PSI, Hulls hit Perfs - Pressure @ 1200 PSI. Staged cement into formation - well holding 1200 PSI, washup - Pumped little water behind cement, Pressure @ 1500 PSI. Closed well in with 1500 PSI. Job complete. Tear down.

15 Sks. @ Perfs, 10 Sks @ 600', 22 Sks. @ 300' To Surface

"Thank You"

Witnessed by George

Customer Signature