

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24848-00-00
Spot: W2NE Sec/Twnshp/Rge: 11-16S-11W
1200 feet from N Section Line, 1800 feet from E Section Line
Lease Name: HOUSKA Well #: 1-11
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3361		225 SX
SURF	8.625	468		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2014 10:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: SAMUEL GARY JR. AND ASSOCIA Phone: (620) 655-4494

Proposed Plugging Method: 07/18/2014- Ordered 75 sx 60/40 pozmix 4% gel cement w/200 # hulls.
07/21/2014- Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel and 400 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2014 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

07/18/2014- Spotted 75 sx cement w/200 # hulls.
07/21/2014- Tagged cement at 2880'. Cut casing at 1487' and pulled casing out of hole. Ran tubing to 1174' and pumped 10 sx gel followed by 125 sx cement w/300 # hulls. Pulled tubing to 744' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 445' and pumped 50 sx cement. Pulled tubing to 195' and pumped 50 sx cement. Cement circulated. POOH and topped off w/15 sx cement. Checked fill up down 3 seconds. Will top off.

GPS: 38.67833 -098.50472

Perfs:

Top	Bot	Thru	Comments
3295	3299		
3286	3290		

KCC WICHITA
AUG 07 2014

Remarks: ALLIED CEMENTING TICKET # 63543

RECEIVED

Plugged through: TBG

District: 04

Signed

Ray Dinkel

8.18.14 CLM

(TECHNICIAN)

(M)

JUL 25 2014