

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20704-00-00
Spot: W2SESENE Sec/Twnshp/Rge: 27-4S-24W
2310 feet from N Section Line, 570 feet from E Section Line
Lease Name: JOSEPH Well #: 1-27
County: NORTON Total Vertical Depth: 3975 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	600		300 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/17/2014 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 07/17/2014 2:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3856 w/50 sx
2nd plug @2075 w/50 sx
3rd plug @1325 w/100 sx
4th plug @650 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY


Plugged through: DP

Received
KANSAS CORPORATION COMMISSION

JUL 31 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed 
(TECHNICIAN)

8-18-14 CKM

JUL 25 2014