

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22496-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 33-18S-10W
1675 feet from S Section Line, 2399 feet from E Section Line
Lease Name: SITTNER ET AL RINGWALD Well #: 1-33
County: RICE Total Vertical Depth: 3390 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3250		
PROD	5.5	3388	1255	125 SX
SURF	8.625	339		175 SX
T1	2.375	3345		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2014 1:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: ALLIANCE WELL SERVICE Phone: (620) 655-4494

Proposed
Plugging
Method:

AS DIRECTED BY KCC

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 07/17/2014 3:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 3250' AND CAP WITH 2 SX'S CEMENT. CUT CASING OFF AT 1255' AND PULL OUT OF HOLE. RUN TUBING IN TO 1250' AND PUMP 10 SXS GEL FOLLOWED BY 35 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 390' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF

Perfs:

Top	Bot	Thru	Comments
3318	3320	CSG	
3312	3315	CSG	
3307	3309	CSG	
3305	3315	CSG	
3303	3305	CSG	
3274	3282	CSG	

KCC WICHITA

JUL 25 2014

RECEIVED

Remarks: ALLIED CEMENT TICKET #063594.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

8-18-14 *ckm*

(TECHNICIAN)