

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Michaels of Xplor Drlg Co has this

date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Gemini Oil Co

Complete Address: 1408 Philtower Bldg Tulsa, OK

Lease Name: Jackson Well No. 1

Location: C E/2 W/2 SW Sec. 30 Twp. 26s Rge. 13 (E)(W)

County: Pratt Total Depth 3330 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Michaels was instructed to plug the well as follows:

287 ft 10 3/4 surface cemented with 275 sacks. 610 ft 8 5/8

surface cemented with 100 sacks. Pulled 300 ft of 8 5/8.

Fill hole to 275 ft, plug, 1/2 sack hulls, 35 sacks cement.

Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks to surface.

This well was moved 660' S of original location.

Very truly yours,


Conservation Division Agent