

15-159-19220-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rice County. Sec. 13 Twp. 185 Rge. 10W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines NE NE NW  
Lease Owner Alpine Oil & Royalty Co., Inc.  
Lease Name Schultz Well No. 1  
Office Address 800 Bitting Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed August 22, 1963 19  
Application for plugging filed July 21, 1969 19  
Application for plugging approved July 22, 1969 19  
Plugging commenced Aug. 1, 1969 19  
Plugging completed Aug. 8, 1969 19  
Reason for abandonment of well or producing formation Nonproductive of oil in commercial quantities  
If a producing well is abandoned, date of last production July 1 1969  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Arbuckle Depth to top 3236 Bottom 3247 Total Depth of Well 3247 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	207 ft	Cemented
				5 1/2"	3238 ft.	2197 feet
	RECEIVED					
	STATE CORPORATION COMMISSION					
	AUG 15 1969					
	CONSERVATION DIVISION					
	Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran plug to 2675 feet, 5 sacks cement from 2675 to 2640.  
Pumped 5 sacks jel, 25 sacks cement, 6 sacks jel, 25 sacks cement, 3 sacks jel and 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.,  
Address 206 East Sixth Street, Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dwight J. Wilson (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Dwight J. Wilson  
800 Bitting Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 1969

My commission expires December 10, 1972

[Signature]  
Evelyn Wanko  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- American Oil & Gas  
Farm- Schultz (twin) No. 1

SEC. 13 T. 18 R. 10W  
NE NE NW

Total Depth. 3247'  
Comm. 6-4-63 Comp. 6-14-63  
Shot or Treated,  
Contractor. Burt Drlg.  
Issued. 12-14-63

County Rice KANSAS



Elevation. 1757' KB

Production. 26 BOPD / W&R

CASING:

8 5/8" 207' cem w/ 150 sx  
5 1/2" 3238' cem w/ 150 sx

Figures Indicate Bottom of Formations.

top soil & clay	30
shale & shells	160
hard sand	180
blue shale	207
shale & redbed	425
anhydrite	488
shale & shells	1197
lime w/ shale streaks	1365
lime & shale	2260
shale & sand	2492
shale & lime	2515
lime	2755
Heebner shale	2759
lime & shale	2870
lime (brown)	2893
lime (Lansing)	2940
lime	3168
shale & lime	3194
Conglomerate	3236
Lime (Arbuckle)	3247
Total Depth	3247 RTD

TOPS: SMP

Topoka	2491
Heebner	2755
Brown Lime	2871
Lansing	2892
Base Kansas City	3168
Conglomerate	3194
Arbuckle	3235

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 15 1969  
CONSERVATION DIVISION  
Wichita, Kansas