

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. MARKET, ROOM 2078
 WICHITA, KS 67202

WELL PLUGGING RECORD
 K.A.R. -82-3-117

API NUMBER 15-009-21804 • 00 • 00

LEASE NAME Disque A

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

WELL NUMBER #1

2970 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR VESS OIL CORPORATION

SEC. 23 TWP. 17S RGE. 11W (E) or (W)

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

COUNTY Barton

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed _____

Character of Well OIL

Plugging Commenced 11/20/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/21/00

The plugging proposal was approved on 11/14/2000 & 11/21/00 (date)
 by Roger Moses; Jay Pfeiffer & Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? no logs were run on well

Producing Formation Arbuckle Depth to Top 3289 Bottom 3292 T.D. 3292

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		Casing Record				
Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	sw and slight oil	3289	92	8-5/8"	209	none
				5-1/2"	3289	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Spot 50 sx 60/40 Pozmix, 10% gel down tubing at 2038' to 1550'; spot 12 sx (36 bbl) 9 ppg gel water 1550' to 900'; circ. 60 sx 60/40 Pozmix, 10% gel 900' to surface. Top off with 10 sx more. Pressure up to 300#. It held steady. 8-5/8 and 5-1/2 annulus - cement in valve: evidence cement circulated on squeeze from 284 to 500'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Well Service, Inc. License No. 6454

Address P.O. Box 384 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK

RECEIVED
 STATE CORPORATION COMMISSION

W. R. Horgan (Employee of Operator) or (Operator) of NOV 9 2000
 above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this

8100 E. 22nd St. N., Bldg. 300
Wichita, KS 67226

22nd day of November 2000

Notary Public

Form CP-4
 Revised 05-88

My Commission Expires:





CHARGE TO: *Ness Oil Corp*
 ADDRESS:
 CITY, STATE, ZIP CODE:

TICKET No 2900

PAGE- 1 OF 11

SERVICE LOCATIONS 1. *Ness City, Mo.* WELL/PROJECT NO. *A#1* LEASE *Disque* COUNTY/PARISH *Barton* STATE *Ks* CITY DATE *11-21-00* OWNER *Same*

2. TICKET TYPE SERVICE SALES CONTRACTOR *Cherokee Well Serv.* RIG NAME/NO. SHIPPED *VIA CIT* DELIVERED TO *Location* ORDER NO.

3. WELL TYPE *O.I* WELL CATEGORY *Workover* JOB PURPOSE *Plug To Abandon* WELL PERMIT NO. WELL LOCATION

4. REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE		AMOUNT	
		LOC	ACCT	DF									
575		1			MILEAGE	40		mil		2	50	100	00
576		1			Pump Service	1		ea		500	20	500	00
581		1			Service Charge	220		1/2		1	100	220	00
		1			Drainage	394.8		1000 mils		175		296	10
329		1			60/40 Poz. 10% Gel	120		gal		5	35	702	00
279		1			Bestonte	20		gal		11	00	220	00

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

x *Basen*
 DATE SIGNED TIME SIGNED A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY		AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	2038	10
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?							
WE UNDERSTOOD AND MET YOUR NEEDS?							
OUR SERVICE WAS PERFORMED WITHOUT DELAY?							
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?					TAX		
ARE YOU SATISFIED WITH OUR SERVICE?		<input type="checkbox"/> YES <input type="checkbox"/> NO			TOTAL		
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND							

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR *Reg. B. Roberts* APPROVAL

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 11-21-20 PAGE NO. 1

CUSTOMER *Ves. O.I. Co.* WELL NO. *A#1* LEASE *Diague* JOB TYPE *Plug In Abrader* TICKET NO. *2900*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	10:00							On loc. set up 18" rig running tubing to 2030'
	10:30		18					Mix 50% R. 60/40 Pz 10% G.C.P.
			7 3/4					Dipl. to 2030'
	10:40							pull to 1550'
	10:50		36					Start mixing G.C.P. 12% mix 36" Cnd. Cir. to surface
	11:10							pull to 900'
			22					Mix Cnd. 22 1/2" Cnd. to surface 60% pull tubing out of hole
	12:00		4			300		haul up to 5 1/2" Csg. pump 2 1/2" cut csg. holding 300psi. Release press. wash and rack up 18" rig. Job Complete.

11/21/20
R. King