

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-22492-00-00

LEASE NAME Frees

WELL NUMBER 1

5000 Ft. from S Section Line

3042 Ft. from E Section Line

SEC. 1 TWP. 17S RGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 11-16-00

Plugging Completed 11-17-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E.22nd. N. Bldg. 300 Wichita, Ks. 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3407'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	274'	None CONSERVATION DIVISION
				4-1/2"	3403'	1600' Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each. TD @ 2960', sanded off bottom to 2900', checked hole, found TD @ 1600', shot pipe @ 1600', pumped 80 sks. cement and 300# hulls, pulled up to 750', pumped 40 sks. cement and 200# hulls, pulled up to 300', pumped 80 sks. cement and circulated to surface. Pulled rest of pipe, well stayed full. 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of November, 2000

[Signature]
Notary Public

My Commission Expires: _____



Form 07
Revised 05-