

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-009-22987-00-00

LEASE NAME Oberle

WELL NUMBER 1

1750 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 36 TWP. 17S RGE. 11W (E) (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 11-30-00

Plugging Completed 12-4-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. N. #300 Wichita, Kansas 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.O. 3263'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	229'	None
				5-1/2"	3260'	1700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3260' and 5 sks. cement. Shot pipe @2000' and 1700'. Pulled up to 1400', pumped 100 sks. cement w/300# hulls, pulled up to 625', pumped 40 sks. cement w/200# hulls, pulled up to 250' and circulated 60 sks. cement to surface. Pulled rest of pipe and topped off with 10 sks. cement, 60/40 pos, 10% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of December, 2000

Jane S. ...
Notary Public

My Commission Expires:



Form CP
Revised 05-