

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24 302 .00 .00

LEASE NAME McClellan "A" #2

WELL NUMBER _____

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 24 TWP. 17 RGE. 11W (E) or (W)

COUNTY Barton

LEASE OPERATOR Grady Bolding Corporation

ADDRESS P.O. Box 486 Ellinwood, Kansas 67526

PHONE# (316) 564-2240 OPERATORS LICENSE NO. 7383

Date Well Completed _____

Character of Well Oil

Plugging Commenced 10-2-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-3-00

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3372'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
TATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	344'	None
				5-1/2"	3377'	2421'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each side. Plugged off bottom with sand to 3250' and 5 sks. cement. Shot pipe @2421', pulled up to 1425', pumped 100 sks. cement and 300# hulls @1425', pulled up to 625', pumped 40 sks. cement and 100# hulls, pulled up to 250', pumped 55 sks. cement, topped off with 5 sks 60/40 pos. 10% Plugging Complete. gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 5th day of October 2000

[Signature]
Notary Public

My Commission Expires: _____

