

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-23,103-00.00

LEASE NAME Harzman

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
1650S  
330 Ft. from W Section Line  
2310E  
990 Ft. from N Section Line

LEASE OPERATOR Energy Three, Inc.

SEC. 26 TWP. 16S RGE. 12W (E) or (W) (W)

ADDRESS P.O. Box 255 Gorham, Kansas 67640-0255

COUNTY Barton

PHONE (785) 483-1292 OPERATORS LICENSE NO. 5430

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 5-16-00

(Oil, Gas, O&A, S&W, Input, Water Supply Well)

Plugging Completed 5-17-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by Case Morris (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	252'	None
				4-1/2"	3450'	1448'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3280' and 4 sks. cement, shot pipe @1448', pumped 70 sks. cement and 300# hulls, pulled up to 800', pumped 40 sks. cement and 100# hulls, pulled to 200' and pumped 60 sks. cement to surface. 60/40 pos, 10% gel. Pulled rest of pipe. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy Three, Inc.

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

MAY 22 2000

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of May, 2000

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CP  
Revised 05-