

**STATE OF KANSAS**  
**STATE CORPORATION COMMISSION**  
 30 S. Market, Room 2078  
 Wichita, KS 67202

**WELL PLUGGING RECORD**  
 K.A.R.-02-3-117

API NUMBER 15-009-23,548 00.00

LEASE NAME Bitter

WELL NUMBER 3

**TYPE OR PRINT**  
**NOTICE: Fill out completely**  
**and return to Cons. Div.**  
**office within 30 days.**

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 5 TWP. 16 RGE. 13W (E) or (W)

COUNTY Barton

LEASE OPERATOR Smith Oil Operations

ADDRESS P.O. Box, 550 Hutchinson, Kansas 67504-550

PHONE# (316) 663-6622 OPERATORS LICENSE NO. 6988

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-31-00

Plugging Completed 11-2-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
				10-3/4"	373'	None
				7"	3340'	1580'

RECEIVED

STATE CORPORATION COMMISSION

NOV 16 2000

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the plugs were placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. Plugged off bottom with sand to 2830' and 7 sks. cement. Shot pipe @1580' pulled 2 jts. pumped 180 sks. cement and 300# hulls @1530', pulled up to 900', pumped 40 sks. cement and 200# hulls, pulled up to 250' and circulated 95 sks. cement to top of hole. 60/40 nos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Smith Oil Operations

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of November, 2000

[Signature]  
 Notary Public

My Commission Expires: \_\_\_\_\_

