

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
115 S. Market, Room 2070  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-009-24,601-00-00

LEASE NAME Grace Schneweis

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

3  
230' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 30 TWP. 17 RGE. 11W (E) of (W)

LEASE OPERATOR Grady Bolding Corporation

COUNTY Barton

ADDRESS P.O. Box 486 Ellinwood, Kansas 67526

Date Well Completed \_\_\_\_\_

PHONE (316) 564-2240 OPERATORS LICENSE NO. 7383

Plugging Commenced 2-1-00

Character of Well Oil

Plugging Completed 2-4-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

When plugging proposal was approved on \_\_\_\_\_ (date)

By Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	289'	None
				5-1/2"	3419'	2380'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.  
Plugged off bottom with sand to 3200' and 5 sks. cement. Shot pipe @2380', pulled up to 1425', pumped 300# hulls with 100 sks. cement, pulled up to 700', pumped 100# hulls with 40 sks. cement, pulled up to 200' and circulated 60 sks. cement with 100# hulls.  
Plugging Complete \_\_\_\_\_ 60/40 pos. 10%  
ge

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated and matters herein contained and the log of the above-described well as filed is correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

FEB 22 2000

CONSERVATION DIVISION SUBSCRIBED AND SWORN TO before me this 8th day of February, 2000

Wichita, Kansas  
**COPY**  
My Commission Expires: \_\_\_\_\_

[Signature]  
Notary Public

IRENE HERZBERG  
State of Kansas  
My Appl. Exp. Aug. 24, 2001

Form 05  
Revised 05