

1 051368

11-16
API NUMBER 15- 151-22,017-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SW, SEC. 19, T 26 S, R 13 W EX

1650 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name McMannis Well # 1

Operator: Bowers Drilling Company, Inc.

County Pratt 145.50

Name & Address 125 N. Market, Suite 1425

Well Total Depth 4477 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour 9 p.m. Day: 16 Month: 11 Year: 19 90

Plugging proposal received from Harvey Moore

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 869-882'

1st plug at 890' with 50 sx cement, 2nd plug at 350' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:30 p.m. Day: 16 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 890' with 50 sx cement,

2nd plug at 350' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement,

Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix, 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
If you did not observe this plugging, STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

DATE NOV 27 1990

INV. NO. 30027

NOV 26 1990