

15-145-01306-00-01

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Little George Oil Co.

Complete Address 225 Sutton Place Wichita Ks.

Lease Name Porteous Well No. 1

Location NE-NE-SE Sec. 31 Twp. 22 Rge. 17 (S) (W)

County Pawnee Total Depth 4310

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kathol Pet. Inc.

Address 900 Sutton Place Wichita Ks. License No. 661

Operation Completed: Hour 10:00 AM Day 20 Month 9 Year 1974

The above well was plugged as follows:

K.B. Elev 2105 - 8 5/8" @ 194' w/175 sacks cement.  
5 1/2" @ 4309' w/175 sacks cement - Recovered. 2708'  
Perf. 4249-53 sanded back to 4200' & 4 sacks cement.  
Hole full of Gel - pumped down 8 5/8"  
2 sacks Hulls - 20 sacks Gel - 1 sack Hulls  
Released wooden Plug  
100 sacks cement 50/50 pozmix 6% Gel. 600# pressure.  
Sun Cementing pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Walter Batthazor  
Well Plugging Supervisor

INVOICED

DATE 9/23/74

INV. NO. 9933-W