

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 28 Twp. 26S Rge. 13W (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Monsanto Chemical Company

Lease Name Strait Well No. 5

Office Address P. O. Box 580, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 1-18 19 51

Application for plugging filed 1-2 19 62

Application for plugging approved 1-4 19 62

Plugging commenced 1-27 19 62

Plugging completed 2-5 19 62

Reason for abandonment of well or producing formation Well had reached its economic limit

If a producing well is abandoned, date of last production 7-10 19 61

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hampel

Producing formation Mississippi Depth to top 4265' Bottom 4285' Total Depth of Well 4285' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	842'	0'
				5-1/2"	4270'	2514'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4250' and dumped 5 sacks cement. Worked and shot 5-1/2" casing free at 2514'. Built rack and slide. Pulled and layed down casing. Bailed down hole. Mudded up to 260' and set 10' rock bridge. Dumped 1 sack Calseal and 5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221, Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF PRATT, ss.

Bruce E. Roll (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce E. Roll

P. O. Box 580, Pratt, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21st day of February 19 62

Van Doubek Notary Public.

My commission expires September 4, 1962

STRAIT WELL No. 5

SW SW SW
SEC. 28-26-13
PRATT COUNTY,
KANSAS

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR: THE R. W. RINE DRILLING COMPANY
STARTED: MAY 23, 1951

FINISHED: JUNE 6, 1951

LOG

SAND	0	-	70	
SAND, SHALE	70	-	450	SYFO @ 400' - 1/2".
RED BED, ROCK	450	-	850	9-5/8" Csg. @ 842' w/420 sx.
SHALE AND SHELLS	850	-	1460	SYFO @ 1000' - 1/2".
SALT AND SHALE	1460	-	1520	SYFO @ 1500' - 1".
SHALE AND SHELLS	1520	-	1850	
SHALE AND LIME	1850	-	2045	SYFO @ 2000' - 1".
LIME	2045	-	2375	
LIME AND SHALE	2375	-	3200	SYFO @ 3228' - 1".
LIME	3200	-	3574	
LIME AND SHALE	3574	-	3835	
LIME	3835	-	3960	SYFO @ 3850' - 1".
LIME	3960	-	4145	
LIME AND SHALE	4145	-	4210	
CHERTY, LIME	4210	-	4230	
LIME	4230	-	4261	
LIME AND CHERT	4261	-	4275	5 1/2" Csg. @ 4270'.

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

I, E. H. SLOYER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE STRAIT WELL No. 5, LOCATED IN THE SW SW SW OF SECTION 28-26-13, PRATT COUNTY, KANSAS.

E. H. Sloyer
SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 12TH DAY OF JUNE, 1951.

R. M. Green
NOTARY PUBLIC

MY COMMISSION EXPIRES DECEMBER 29, 1952.