


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County. Sec. 30 Twp. 26 Rge. 13 ~~12~~ (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW SE
Lease Owner D. E. Dunne, Jr.
Lease Name Tobias Well No. 1
Office Address 300 Schweiter Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 24 19.55
Application for plugging filed July 24 19.55
Application for plugging approved July 25 19.55
Plugging commenced July 24 19.55
Plugging completed July 24 19.55
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4568' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug set at 300' with 1 1/2 Gal. Hulls, 20 sacks cement
Added mud up to 40'. 1 1/4 sacks Hulls then top plug with
10 Sacks of cement. Plugged up to surface.
All the proceeding went through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to D. E. Dunne, Jr.
Address 300 Schweiter Building, Wichita

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. E. Dunne, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *D. E. Dunne Jr.*
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26 day of August, 1955.

Almeda Gray
Notary Public.

My commission expires September 9, 1957

PLUGGING
PLK SEC 30 T 26 R 13 W
BOOK PAGE 137 LINE 10

WELL LOG

COMPANY **D. E. Dunne, Jr.**

SEC. 30 T. 26 R. 13W

FARM **TOBIAS**

NO. **1**

LOC. **S7 NW SE**


TOTAL DEPTH **4568'**

COUNTY **Pratt County**

COMM. **July 9, 1955**

COMP. **July 24, 1955**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 855' w/500 sax.**

ELEVATION **1959' DT**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

430	Red Bed
650	Sand & Clay
845	Sand, Clay & Shale
870	Anhydrite
1580	Shale & Shells
3792	Lime & Shale
3819	Shale
4254	Lime
4300	Lime & Shale
4328	Mississippi
4352	Lime & Shale
4354	Kinderhook
4434	Viola
4509	Simpson
4528	Shale & Lime
4568	Arbuckle
4568	RTD

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 27 1955
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of SEDGWICK } SS:

I, Robert F. White of Garvey Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the TOBIAS #1 well

PLUGGING
 FILE SEC 30 T 26 R 13W
 BOOK PAGE 37 LINE 10

Robert F. White

Subscribed and sworn to before me this 5th day of August 19 55

My Commission Expires: 10-27-56

Marjorie Bradshaw
 NOTARY PUBLIC