

TO:   
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21804-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 23-17S-11W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: DISQUE A Well Number: 1  
County: BARTON Total Vertical Depth: 3292 feet

Operator License No.: 5030  
Operator Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.62 feet: 209 150 SX CMT  
Production: Size 5.5 feet: 3289 100 SX CMT 106.99  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2000 10:00 AM

Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.

Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel and 20 sxs Benonite Spacer.  
O.H. 3289' - 3292'.  
Squeeze casing at 284' - 500' w/250 sxs.  
F.L. at 300'.

Plugging Proposal Received By: HUBERT DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/21/2000 12:15 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Cheyenne Well Service rigged up and ran tubing 2038'.  
Swift Service tied on tubing and pumped 50 sxs cement.  
Pulled tubing to 1550' - tied onto and pumped 12 sxs gel.  
Pulled tubing to 900' and circulated cement with 60 sxs.  
Laid tubing out - tied onto 5 1/2" and pumped pressure with 10 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 2000

Remarks: SWIFT SERVICES, INC.

CONSERVATION DIVISION  
Wichita, Kansas

Plugged through: TBG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 12/1/00

INV. NO. 2001061051

Form CP-2/3

NOV 28 2000

PETROLEUM ENERGY INC  
710 ONE TWENTY BLDG  
WICHITA, KS 67202

#1 DISQUE "A"

23-17-11W  
SW SW NW

CONTR WHITE & ELLIS DRILLING CTY BARTON

GEOL

FIELD KRAFT-PRUSA

1854 KB CM 1/9/80 CARD ISSUED 3/13/80 IP P 74 BOPD & WTR  
ARB OH 3289-3292

+	+	+
+	+	+
+	+	+

API 15-009-21,804

SMP	TOPS	DEPTH	DATUM
ANH		640	+1214
TOP		2568	-714
HEEB		2902	-1048
TOR		2916	-1062
DOUG		2932	-1078
BR LM		3006	-1152
LANS		3019	-1165
ARB		3286	-1432
RTD		3292	-1438

8-5/8" 209/150sx, 5 1/8" 3289/100sx  
DST (1) 3030-3140/30-30-30-30, REC  
70' M W/SPKS 0, SIP 232-201#, FP  
63-63/73-73#  
DST (2) 3288-3292/30-30-30-30, REC  
820' GSY OCM, 1225' GSY O, 175' OC  
WTR, 480' WTR, SIP 1060-1071#, FP  
317-945/1060-1060#  
MICT - CO, (ARB OH) FU 2700' F (800'  
O & 1900' WTR), SWB 20.29 BO/4 HRS &  
31 BW, POP, P 74 BOPD & WTR

# INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS