

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22492-00-00  
Spot: NENENW Sec/Twnshp/Rge: 1-17S-11W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: FREES Well Number: 1  
County: BARTON Total Vertical Depth: 3407 feet

Operator License No.: 5030  
Operator Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 274 185 SX CMT  
Production: Size 4.5 feet: 3403 175 SX CMT 110.73  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/17/2000 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered out 240 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Prod. Perfs at 3369' - 3370'; 3385' - 3387'.  
Open hole at 3403' - 3407'.  
CIBP's at 3380' and 3402'.  
Shot lose at 1590'.

Plugging Proposal Received By: HUBERT DEINES  
Date/Time Plugging Completed: 11/17/2000 1:45 PM

Witness Type: Plugging Operations Partially Witnessed  
KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off bottom to 2900'.  
Rigged up on 4 1/2" and shot lose at 1590'.  
Pulled up to 1500'.  
Allied tied onto and pumped 80 sxs with 300# hulls and displaced to 1600'.  
Pulled casing up to 750' and spotted 40 sxs with 200# hulls.  
Pulled casing to 300' and circulated cement with 80 sxs.  
Laid casing out.  
Hole standing full of cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 2000

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed

*Jay Pfeifer*

(TECHNICIAN)

INVOICED

DATE 12/1/00

INV. NO. 2001061051

Form CP-2/3

NOV 28 2000

REIF OIL OPERATIONS

BOX 298

HOISINGTON, KS 67544

CONTR FUTURE DRILLING INC

#1 FREES

CTY BARTON

1-17-11W

50'N&75'W

NE NE NW

GEOL JIM MUSGROVE

FIELD KRAFT-PRUSA NE EXT (1/8 S)

R 1923 KB CM 9/8/81

CARD

ISSUED

12/3/81 IP P 25 BO & 20 BWPD

ARB 3369-3370

+	+	+
+	+	+
+	+	+

API 15-009-22,492

LOG	TOPS	DEPTH	DATUM
ANH	696	+1227	
B ANH	713	+1210	
HEEB	2944	-1021	
TOR	2966	-1043	
DOUG	2979	-1056	
BR LM	3044	-1121	
LANS	3058	-1135	
BKC	3337	-1414	
CONG	3345	-1422	
ARB	3352	-1429	
RTD	3404	-1481	
LTD	3407	-1484	

8 5/8"274/185sx; 4 1/2"3403/175sx  
 DST (1) 2890-2920/30-30-30-30, REC 30' M, SQ ON TOP OF TOOL, SIP 803-782#, FP 64-43/53-43#  
 DST (2) 3061-3106(LKC)/45-30-45-30, GTS 4", GTSTM, REC 40' GCM, SIP 117-64#, FP 32-43/43-43#  
 DST (3) 3365-74 (ARB)/45-45-45-45, 150' GIP, REC 280' CL O, 120' OCW, 60' SOCW, 120' W, SIP 1138-1117#, FP 53-117/138-191#  
 MICT CO (ARB OH), SWB 2 1/2 BFPH, 10% O, NAT, FU 1800' FL (8% O, 92% W), PB @ 3390, PF (ARB) INTV NA, SWB 20 BFPH (2% O), PB @ 3375, PF (ARB), 3369-70, SWB 3 BOPH, TR WTR, FU 800' FL (750' O & 50' WTR), AC 250G, SWB DWN & REC 15 BFPH (75% O, 25% WTR), FU 2800' FL, (75% O, 25% WTR), POP, P 25 BO & 20 BWPD

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS