

4-020139

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-22,261-00-00

SW NE NW /4 SEC. 25, 16 S, 13 W
4290 feet from S section line
3630 feet from E section line

Operator license# 31086

Lease: Allen Well # 1

Operator: Richlan Drilling

County: Barton 110, 94

Address: 598 2nd Avenue
Beaver, Kansas 67525

Well total depth 3398 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 371 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 10:00 A.M. Day: 23 Month: June Year: 2000

Plugging proposal received from: Joe Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Open hole and perf at 3312' - 3316'; 3272' - 3275'.

Cut casing off at 1800'.

RECEIVED
ST. CORPORATION COMMISSION

JUL 6 2000

Plugging Proposal Received by: Jay Pfeifer
Plugging operations attended by agent? All , Part , None

Conservation Division
Wichita, Kansas

Completed: Hour: 1:00 P.M., Day: 23 Month: June, Year: 2000

Actual plugging report: 8 5/8" set at 371' w/200 sxs. 5 1/2" set at 3394' w/150 sxs.

Sanded off well to 3260' and topped with 5 sxs cement with a dump bailer.

Cut casing off at 1800'.

Pulled casing to 1635' - tied onto and pumped 75 sxs with 200# hulls.

Pulled casing to 925' - tied onto and spotted 75 sxs with 300# hulls.

Pulled casing to 400' - tied onto and circulated cement with 60 sxs.

Pulled casing out of hole.

Hole standing full of cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1918 GL

I did / did not observe the plugging.

Jay Pfeifer
(agent)

INVOICED

DATE 7/16/00

NO. 1060027

Form CR-2/3