

4-020140

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-22,699-00-00

NW NE NW /4 SEC. 25 , 16 S, 13 W
4950 feet from S section line
3630 feet from E section line

Operator license# 31086

Lease: Allen Well # 2
County: Barton 110.60

Operator: Richlan Drilling 6/22
Address: 598 2nd Avenue
Beaver, Kansas 67525

Well total depth 3403 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 614 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 9:00 A.M. Day: 22 Month: June Year: 2000

Plugging proposal received from: Joe Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Ordered out 305 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
ST. CORPORATION COMMISSION
JUL 6 2000
Conservation Division
Wichita, Kansas

Plugging Proposal Received by: Bruce Basye

Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:30 P.M. , Day: 22 Month: June , Year: 2000

Actual plugging report: 8 5/8" set at 614' w/400 sxs. 5 1/2" set at 3402' w/150 sxs.
Sanded back to 3350' and topped with 5 sxs cement using a dump bailer.
Cut casing at 1650' - would not free. Pumped into could not get a rate.
Came up casing and cut at 1200' - would not free. Pumped into - could not get a rate.
Came up casing to 800' - cut lose.
Tied onto 5 1/2" - circulated cement with 175 sxs cement with 500# hulls.
Stuck casing at 750'.
Backed off top joint.
Hole standing full of cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1932 GL

I did / did not observe the plugging.

Jay Pfeifer
(agent)

INVOICED
DATE 7/10/00
NW NE 1060027

Form CP-273
R