

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22987-00-00
Spot: N2SENESEW Sec/Twnshp/Rge: 36-17S-11W
1750 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: OBERLE Well Number: 1
County: BARTON Total Vertical Depth: 3263 feet

Operator License No.: 5030
Operator Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 229 150 SX CMT
Production: Size 5.5 feet: 3260 125 SX CMT 106.05
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2000 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Open hole 3260' - 3263'.
Shot casing at 1706'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/05/2000 11:30 AM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back to 3200' and topped with 5 sxs cement with a dump bailer.
Rigged up on 5 1/2" and shot free at 1706'.
Pulled up to 1400' and pumped 100 sxs with 300# hulls.
Pulled to 625' and spotted 40 sxs with 200# hulls.
Pulled to 250' and circulated cement with 60 sxs.
Pulled 5 1/2" out of the hole.
Topped with 10 sxs cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY. SPOT LOCATION READS AS FOLLOWS: 100' N. SESEW 36-17-11W.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 12/11/00

TIME 2001061162


Form CP-2/3

DEC 06 2000

PETROLEUM ENERGY, INC. 36-17-11W
 415 1ST NATIONAL BANK BUILDING #1 OBERLE 1750' FSL &
 WICHITA, KS 67202 2310' FWL, SW/4
 CONTR DURE DRLLG. CO., INC. CTY BARTON

GEOL _____ FIELD BLOOMER

1816 KB
 ELV 1811 GL SPD 12/20/82 CARD ISSUED 2/3/83 IP P 81 BOPD, NW
 API 15-009-22,987 ARB OH 3260.5-3263



SMP	Tops	Depth/Datum	8 5/8 " 229/150SX; 5 1/2 " 3260.5/145SX
			DST (1) 2996-3016 (LANS) / 30-30-30-30, REC 80' WM, SIP 604-334#, FP 65-65 / 86-86#
HEEB	2855-1039	DST (2) 3229-3263 (ARB) / 30-30-30-30, REC 250' VHO & GCM, NW, SIP 571-517#, FP 75-119 / 129-144#
TOR	2874-1058	
DOUG	2885-1069	MICT - CO, (ARB OH), SWB 2.5 BOPH, ONFU 1175' FL, NAT, T&R, POP, P 81 BOPD - NW, 1/27/83
BR LM	2967-1151	
LANS	2982-1166	
ARB	3259-1443	
RTD	3263-1447	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS