

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24302-00-00  
Spot: CNENESE Sec/Twnshp/Rge: 24-17S-11W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: MCLEAN A Well Number: 2  
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 7383  
Operator Name: BOLDING, GRADY CORPORATIO  
Address: PO BOX 486  
ELLINWOOD, KS 67526

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 344  
Production: Size 5.5 feet: 3377  
Liner: Size \_\_\_\_\_ feet:

109.59

103

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/3/00 8:30:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 564-2240

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Prod Perfs at 3301' - 3308'.  
Shot casing off at 2422'.

Plugging Proposal Received By: HUBERT DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/03/2000 10:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 344' w/160 sxs. 5 1/2" set at 3377' w/150 sxs.  
Sanded back casing to 3250' and topped with 5 sxs cement with a dump bailer.  
Shot casing off at 2422'.  
Pulled casing to 1425' - tied onto and pumped 100 sxs w/300# hulls.  
Pulled casing to 625' - tied onto and spotted 40 sxs w/100# hulls.  
Pulled casing to 250' - tied onto and circulated cement with 55 sxs.  
Pulled casing out of the hole - topped with 5 sxs.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 16 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*

(TECHNICIAN)

INVOICED

DATE 10/17/00

INV. NO. 2001060840

OCT 06 2000

BOGER BROTHERS DRILLING, INC  
GREAT BEND, KS 67530

24-17 -11W  
NE NE SE

#2 MCLEAN "A"

site: 2 N & 2-1/2 E OF CLAFLIN, KS  
contr: BOGER BROTHERS DRILLING  
geol: JAMES C. MUSGROVE

city: BARTON  
field: KRAFT-PRUSA

API 15-009-24302

fr date 02/02/88    spd date 02/19/88    drlg comp 02/25/88    card issued 05/11/88    last revised 05/11/88


ELV: 1846 KB LOG  
tops.....depth/datum  
ANH.....609 +1237  
HEEB.....2876 -1030  
TOR.....2895 -1049  
DOUG.....2906 -1060  
BR LM.....2988 -1142  
LANS.....3002 -1156  
BKC.....3261 -1415  
ARB.....3277 -1431  
RTD.....3372 -1526

IP status:  
OIL, P 87 BO & 21 BWPD, ARB 3301-3308,  
CSG: 8-5/8" 344 / 160 SX, 5-1/2" 3372 / 150 SX  
NO CORES  
DST (1) 3254-3300 (PENN, ARB), / 30-30-30-30, SB,  
REC 1230' CLEAN GSY OIL ISIP 984# FSIP 976# IFP  
117# -268# FFP 344# -427# IHP 1607# FHP 1597#  
DST (2) 3300-3318 (ARB), / 30-30-30-30, SB, REC 2210'  
CLEAN GSY OIL ISIP 1010# FSIP 1010# IFP 267#  
-554# FFP 689# -807# IHP 1628# FHP 1620#  
MICT - CO, PF (ARB) 3301-3308, W / 2 SPF, AC 400 GAL  
(15% DS/FE), SWB DWN, GSO, SET 2-7/8" TBG AT 3368,  
POP, P 87 BO & 21 BWPD, 3/15/88

COPYRIGHT 1988  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS