

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24122-00-00  
Spot: E2NENWSE Sec/Twnshp/Rge: 24-17S-11W  
2310 feet from S Section Line, 1420 feet from E Section Line  
Lease/Unit Name: MCLEAN Well Number: 1  
County: BARTON Total Vertical Depth: 3356 feet

Operator License No.: 7383

Conductor Pipe: Size

feet:

Operator Name: BOLDING, GRADY CORPORATIO

Surface Casing: Size 8.625

feet: 343

Address: PO BOX 486  
ELLINWOOD, KS 67526

10/3

Production: Size 5.5

feet: 3351

Liner: Size

feet:

109.07

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/3/00 8:30:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: GRADY BOLDING

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 564-2240

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Prod.Perfs at 3025' - 3028'; 3045' - 3048'; 3072' - 3076'; 3304' - 3306'.  
CIBP at 3125'. Shot casing off at 2406'.

Plugging Proposal Received By: HUBERT DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/03/2000 11:30 AM

KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

8 5/8" set at 343' w/200 sx. 5 1/2" set at 3351' w/125 sxs.  
Sanded back casing to 2975' and topped w/5 sxs cement using a dump bailer.  
Shot casing off at 2406'.  
Pulled casing to 1425' - tied onto and pumped 100 sxs w/300# hulls.  
Pulled casing to 625' - tied onto and spotted 40 sxs w/100# hulls.  
Pulled casing to 250' - tied onto and circulated cement w/55 sxs.  
Pulled casing out of the hole.  
Hole standing full of cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 2000

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENT COMPANY.

Plugged through: CSG

District: 04

Signed

*Jay Pfeifer*

(TECHNICIAN)

INVOICED

DATE 10/17/00

INV. NO. 2001060840

Form CP-2/3

OCT 06 2000


MUSGROVE PETROLEUM CORPORATION  
P.O. BOX 1162 #1 MCLEAN

24-17-11W  
100'W.

GREAT BEND, KS. 67530  
CONTR BOGER BROTHERS DRILLING CITY BARTON

C N/2 N/2 SE

GEOL JAMES C. MUSGROVE FIELD KRAFT-PRUSA



ELV 1841 KB SPD 12/9/85 CARD ISSUED 3/6/86 IP P 75 BO & 75 BWPD  
1836 GL DRLG COMP 12/15/85 LKC 3025-3076 OA  
ARB 3304-3306

LOG	Tops	Depth/Datum	API 15-009-24,122
ANH	.....	601 : 1240	8 5/8 " 343 / 200SX, 5 1/2 " 3351 / 125SX
HEEB	.....	2867-1026	DST (1) 3014-3075 (LANS) / 30-30-30-30, (2ND OP) GTS / NT,
TOR	.....	2889-1048	TSTM, REC 300' HOCM, 240' MDY GSY OIL, SIP 302-297#, FP
LANS	.....	2994-1153	184-194 / 209-218#
BKC	.....	3235-1394	DST (2) 3127-3190 (LKC) / 45-30-30-30, REC 10' M, SIP 293-
CONG	.....	3259-1418	276#, FP 59-67 / 75-84#
ARB	.....	3294-1453	DST (3) 3252-3298 (ARB) / 30-30-0-0, REC 5' M, ISIP 84#, IFP
PBTD	.....	3334-1493	50-58#
LTD	.....	3346-1505	DST (4) 3252-3308 (ARB) / 30-30-30-30, REC 1200' HOC GSY
RTD	.....	3356-1515	WTR, SIP 1044-1035#, FP 126-285 / 411-563#
			MICT - CO, PF (ARB) 3304-3306, W / 2 SPF, AC 200 GAL, SWB 8
			BFPH (50% OIL) 700' OFF BTM, SET PLUG (DEPTH NA), PF
			(LANS) 3072-3076, 3045-3048 & 3025-3028, W / 2 SPF, AC 5000
			GAL, SWB DWN, GSO & G, PULL PLUG, T&R, POP, P 75 BO &
			75 BWPD (GR 39°), COMMINGLED, 1/10/86

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS