

4-020141

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,443-00-00
150'S.of
SE SE NE /4 SEC. 24 , 16 S , 13 W
2820 feet from S section line
330 feet from E section line

Operator license# 31086

Lease: Christians Well # AA-1

Operator: Richlan Drilling

County: Barton 110.70

Address: 598 2nd Avenue
Beaver, Kansas 67525

Well total depth 3406 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 350 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S.& W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 8:00 A.M. Day: 27 Month: June Year: 2000

Plugging proposal received from: Joe Strube

Company: D.S.& W. Well Servicing, Inc. Phone: 316-587-3361

Were: Ordered out 250 sxs 60/40 pozmix - 10% gel - 600# hulls.
Prod.Perf and open hole at 2992' - 2998'; 3146' - 3154'; 3175' - 3181'; 3401' - 3405'.
Well parted at 1400' at collar.

RECEIVED
ST. CORPORATION COMMISSION

JUL 6 2000

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[] Conservation Division
Wichita, Kansas

Completed: Hour: 10:00 A.M., Day: 27 Month: June, Year: 2000

Actual plugging report: 8 5/8" set at 350' w/165 sxs. 5 1/2" set at 3401' w/160 sxs.

Sanded back to 2930' and topped with 5 sxs cement.

Casing parted at 1400'

Pulled casing to 1300' - tied onto and pumped 90 sxs with 500# hulls.

Pulled casing to 900' - tied onto and spotted 40 sxs with 100# hulls.

Pulled casing to 500' - tied onto and circulated cement with 60 sxs.

Pulled casing out of hole.

Hole standing full of cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING . Elevation: 1928 GL

I did[X] / did not[] observe the plugging.

INVOICED

DATE 7/10/00

INV. NO. 1060027

Jay Pfeiffer
(agent)

Form CP-2/3