

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23548-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 5-16S-13W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: BITTER Well Number: 3  
County: BARTON Total Vertical Depth: 3375 feet

Operator License No.: 6988  
Operator Name: SMITH OIL OPERATIONS  
Address: 327 WEST 4TH  
HUTCHINSON, KS 67504

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 10.75 feet: 373 250 SXS CMT  
Production: Size 7 feet: 3340 125 SXS CMT  
Liner: Size \_\_\_\_\_ feet:

11/2  
109.69

Well Type: SWD UIC Docket No: D24285.0 Date/Time to Plug: 11/02/2000 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/02/2000 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2830' and dumped 7 sxs cement.  
Shot off pipe at 1575'.  
Pulled to 1525' and pumped 180 sxs 60/40 pozmix - 10% gel cement with 300# hulls.  
Pulled to 900' and pumped 40 sxs cement with 200# hulls.  
Pulled to 250' and circulated with 95 sxs.

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 9 2000

110 INVOICED

DATE 11/9/00

INV. NO. 2001060954

Form CP-2/3

NOV 08 2000  
CONSERVATION DIVISION  
Wichita, Kansas

DERRICK-AMERICAN OIL, INC.  
225 N. MARKET, #130

#3 BITTER

5-16-13W  
NW NW NE


WICHITA, KS 67202

CONTR DUKE DRILLING CO.

CTY BARTON

GEOLOG MARK A. THOMPSON

FIELD TRAPP



ELV 1904 KBSPD, 5/25/84 CARD ISSUED 10/18/84 IP OIL WELL  
1899 GL ARB OH 3340-3375

SMP	Tops	Depth/Datum	API 15-009-23,548
			10 3/4 " 373 / 250SX, 7" 3340 / 125SX
			DST (1) 3330-41 (ARB) / 30-27-30-30, REG 15' SOCM (18% OIL, 5% G, 15% W, 62% M), 62' HOCM (70% OIL, 5% G, 10% W, 15% M), SIP 1108-1105#, FP 65-69 / 84-86#, HP 1793-1782#
*ANH	.....	874 + 1030	MICT - CO, (ARB OH), DD 3375 TD, AC 250G (15% DEMUL), SWB DWN, POP 10/2/84
HEEB	.....	3007-1103	
LANS	.....	3077-1173	
BKC	.....	3288-1384	
ARB	.....	3336-1432	
RTD	.....	3341-1437	
DDTD	.....	3375-1471	
*DRILLERS TOP			

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS