

4-020107

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-04,010-00-00

SE SE NE /4 SEC. 32 , 17 S, 12 (W)
2970 feet from S section line
330 feet from E section line

Operator license# 7030

Lease: Hoefliner Well # 1

Operator: John Roy Evans

County: Barton

Address: P.O. Box 385
Claflin, Kansas 67525

Well total depth 3357 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 724 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231 - Claflin, Kansas 67525

Company to plug at: Hour: 10:00 A.M. Day: 11 Month: February Year: 2000

Plugging proposal received from: Brian Frinzel

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Ordered out 220 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well Drilled 11-05-55.
Cut off casing at 1900'.
Production Perfs at 3120' - 3236'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 11 Month: February, Year: 2000

Actual plugging report: 8 5/8" set at 724' w/350 sxs. 5 1/2" set at 3357' w/125 sxs cmt.
Sanded off to 2820' and topped with 5 sxs cement with dump bailer.
Cut casing off at 1900'.
Pulled casing to 1440' - tied onto and pumped 100 sxs with 300# hulls.
Pulled casing to 750' - tied onto and spotted 50 sxs with 100# hulls.
Pulled casing to 250' - tied onto and circulated cement with 70 sxs cement and 100# hulls.
Pulled casing out of the hole.
Hole standing full of cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X Elevation: 1824 GL

I did [X] / did not [] observe the plugging.

INVOICED

DATE 2/16/00
INV. NO. 061259

[Signature]
RECEIVED (agent)
STATE CORPORATION COMMISSION

FFR 16 2000

Form CP-2/3

CONSERVATION DIVISION
Wichita, Kansas

(Handwritten mark)