

To: 1 051683 6-23  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,328-0000  
C NE NW  
SEC. 14, T. 34 S, R. 20 W/E  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30972  
Operator: Bishop Operating Company, Inc.  
Name & Address P.O. Box 1807  
Hutchinson, KS 67504

Lease Name G.C. Lemon Well # 11  
County Comanche  
Well Total Depth 4820 156.65 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 784

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 11:45 a.m. Day: 23 Month: 6 Year: 19 93

Plugging proposal received from Vernon Duntz  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4808' w/150 sx cement, Perfs at 4757-64'  
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 23 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs.hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 700 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
6-28-93  
JUN 28 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 7-9-93  
OBSERVE THIS PLUGGING.

Signed Richard W. Lacey  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 7-9-93  
INV. NO. 38082

