

To: 1 051667 6-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,318-0000
C NW NE, SEC. 14, T. 34 S, R. 20 W/EK

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

4620 feet from S section line
1980 feet from E section line

Operator: Bishop Operating Company, Inc.
Name &

Lease Name L.W. Rhodes Well # 3

Address P.O. Box 1807
Hutchinson, KS 67504

County Comanche 171.53

Well Total Depth 5278 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 772

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 1:50 p.m. Day: 15 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4861' w/200 sx cement, Perfs at 4770-78', Tubing fish top at 4000'

1st plug sand back to 3950' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 p.m. Day: 15 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3950' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 6-24-93

Signed Richard W. Lacey
(TECHNICIAN)

WELL NO. 37988

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1993
6-18-93
CONSERVATION DIVISION
Wichita, Kansas