

To: 1 051684
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-23

API NUMBER 15- 033-20,308-0000
C SE NW, SEC. 14, T. 34 S, R. 20 W/E
3300 feet from S section line
3300 feet from E section line
Lease Name G.C. Lemon Well # 9
County Comanche
Well Total Depth 4840 157.30 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 769

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972
Operator: Bishop Operating Company, Inc.
Name &
Address P.O. Box 1807
Hutchinson, KS 67504

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 10:30 a.m. Day: 23 Month: 6 Year: 19 93

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

was: 5 1/2" at 4839' w/100 sx cement, Perfs at 4766-71'

1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls and 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:10 a.m. Day: 23 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, and 125 sx cement. Maximum pressure 750 psi and shut in 450 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-9-93

INV. NO. 38081

Signed Richard M. Lacey (TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION 6-28-93 JUN 28 1993

15-033-20308-0000

K. R. M. PETROLEUM CORPORATION
 817 17TH ST. STE. 820
 DENVER, CO 80202

#9 G. C. LEMON

14-34-20W
 C SE NW

CONTR H-30 INC.

CTY COMANCHE

GEOL COPELAND LANOES

FIELD LEMON RANCH

W 1771 KB CM 8/13/79 ^{CARD} ISSUED 11/15/79 IP F 216 MCFGPD
 & 216 BOPD
 KC 4766-71

API 15-033-20,308

+	+	+
+	*	+
+	+	+

RECEIVED
 STATE CORPORATION COMMISSION

APR 2 1993

4-2-93
 CONSERVATION DIVISION
 Wichita, Kansas

LOG	TOPS	DEPTH	DATUM
CO GR	2644	-873	
COTTWD	2820	-1049	
WAB	3190	-1419	
ELGIN	4005	-2234	
HEEB	4134	-2363	
TOR	4162	-2391	
LKC	4334	-2563	
STK	4744	-2973	
SWOPE	4765	-2994	
HUSH	4796	-3025	
HERT	4804	-3033	
RTO	4840	-3069	
PBTD	4797	-3026	

16" 60, 8-5/8" 769/500sx, 5 1/2" 4839/100sx
 Ø (1) 4771-87/REC NA
 DST (1) 4740-4787/30-60-60-120, GTS 5"
 (2ND OPEN) GA 15.4 MCF/10", 16.7
 MCF/20" & STAB @ 17.2, REC 35' V SL
 OCM, SIP 1579-1737#, FP 106-53/85-
 21#, HP 2400-2369#
 MICT - CO, PF 4766-71, AC 5000 GAL & 8
 BS, SWB DWN, KO FLO, SI, GOR = 1000
 CFPB

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS