

To: 1 051686 6-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,289-0000
C SE NE, SEC. 14, T 34 S, R 20 W/EX
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972
Operator: Bishop Operating Company Inc.
Name:
Address P.O. Box 1807
Hutchinson, KS 67504

Lease Name L.W. Rhoades Well # 1
County Comanche
Well Total Depth 4830 156.97 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 782

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 2 p.m. Day: 23 Month: 6 Year: 19 93

Plugging proposal received from Vernon Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4824' w/100 sx cement, Perfs at 4763-67'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8.5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 p.m. Day: 23 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 5 1/2" casing. JUN 28 1993
(If additional description is necessary, use BACK of this form.) 6-28-93

INVOICED
I (did / did not) observe this plugging.

DATE: 7-9-93
INV. NO. 38080

Signed R. Paul W. Lacey
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

15-033-20289-0000

K.R.M. PETROLEUM CORP.
817 17TH ST.
DENVER, CO 80202

#1 L.W. RHOADES

14-34-20W
C SE NE

CONTR XPLOR DRILLING

CTRY COMANCHE

GEOLOGICAL

FIELD LEMON RANCH EXT (1/8 N)

C 1771 KB CM 6/6/79 CARD ISSUED 9/8/79 IP F 48 BOPD, NW
& 48 MCFGPD
SWOPE 4763-67

+	+	+
+	+	+
+	+	+

API 15-033-20,289

LOG	TOPS	DEPTH	DATUM
CO GR	2640	-869	
COTTWO	2815	-1044	
WAB	3190	-1419	
ELG SD	4022	-2251	
HEEB	4150	-2379	
TOR	4160	-2389	
LKC	4338	-2567	
STARK SH	4744	-2973	
SWOPE	4764	-2993	
HUSH	4796	-3025	
HERTHA	4803	-3032	
LTD	4825	-3054	
RTD	4830	-3059	

8-5/8; 782/110sx, 5 1/2" 4824/100sx
& (1) 4766-82, FULL REC
DST (1) 4740-82 (LKC-SWOPE)/30-60-60-
120, 60' MO, 60' OCM, SIP 471-
1496#, FP 37-34/50-50#, HP 2313-
2274#
MICT - CO, PF (SWOPE) 16/4763-67, AC
5000 (15%) & 10 BS, SWB DWN & FLO 48
BOPD, NW & 48 MCFGPD, SI, GOR 1000:1

RECEIVED
STATE CORPORATION COMMISSION

APR 2 1993
4-2-93
CONSERVATION DIVISION
Wichita, Kansas

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MAR 31 1993 03:52PM BISHOP