

1 090272 4-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Operator: Bishop Operating Company, Inc.
Name:
Address P.O. Box 1807
Hutchinson, KS 67504

API NUMBER 15- 033-20,288-00-01 : 95 K

C NE SE, SEC. 14, T 34 S, R 20 W
1980 feet from S section line
660 feet from E section line

Lease Name G.C. Lemon Well # 3

County Comanche 156.97

Well Total Depth 4830 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 667

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☒ SHD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 8:30 a.m. Day: 23 Month: 4 Year: 19 93

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4830' w/125 sx cement, Perfs at 4768-78'

1st plug sand back to 4710' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 9:10 a.m. Day: 23 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4710' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4100' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 5-11-93
WV. NO. 37662
observe this plugging.

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1993
4-28-93
CONSERVATION DIVISION
Wichita, Kansas

15-033-20288-00-01

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1993
CONSERVATION DIVISION
Wichita, Kansas

K.R.M. PETROLEUM CORP.
817 17TH ST.

14-34-20W
C NE SE

DENVER, CO 80202
CONTR XPLOR DRILLING CO.

#G.2
LEMON
CTY COMANCHE

GEOL FIELD LEMON RANCH CONF

1766 KB CM 3/31/79 CARD ISSUED 6/23/79 IP F 170 B0 & 109

MCFGPD, NW
LKC 476B-78

API 15-033-20,288

LOG	TOPS	DEPTH	DATUM
CO GR	2640	- 874	
COTTWD	2815	-1049	
WAB	3200	-1434	
ELG SD	4025	-2259	
HEEB	4160	-2394	
TOR	4172	-2406	
LKC	4347	-2581	
SWOPE	4768	-3002	
LTD	4828	-3062	
RTD	4830	-3064	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

667' w/700 SX
8-5/8" 667SX 5 1/2" 4830/125SX
Ø (1) 4764-79, REC 16'
DST (1) 4761-79/30-90, GTS 6", GA 180
MCFGPD, OTS 20", REC 240 CL O,
120' FROGGY O, NW, ISIP 1737#, IFP
83#
MICT - CO, PF (SWOPE) 476B-78, F 34
BOPH & GAS THRU 1/2" OK/5HRS, FTP 480#
AC 2000 & 15 BS, SI F 170 B0 & 109
MCFGPD, NW GOR 641

+	+	+
+	+	+
+	+	+

FILE 31 793 03-2111 BISHOP

1