

To: 1 031107
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

20792-0000
API NUMBER 15- 033-20,972

App. NW SE SEC. 14, T 34 S, R 20 W/E
2080 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3882

Lease Name Lemon Well # 14-10
County Comanche 212.22

Operator: Samuel Gary Jr. & Associates, Inc.
Name & Address 1775 Sherman Street, Suite 1925
Denver, CO 80203

Well Total Depth 6530 feet
Conductor Pipe: Size 13" feet 60
Surface Casing: Size 8 5/8 feet 670

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Triad Drilling License Number 7345

Address P.O. Box 1034, Woodward, OK 73802

Company to plug at: Hour: 1 p.m. Day: 8 Month: 10 Year: 19 90

Plugging proposal received from Dan Hall

(company name) Samuel Gary Jr. & Associates, Inc. (phone) 803-831-4673

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 774'

- 1st plug at 4940' with 90 sx cement, 2nd plug at 700' with 50 sx cement,
- 3rd plug at 350' with 25 sx cement, 4th plug at 40-0' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement,
- 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5 p.m. Day: 8 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 4940' with 90 sx cement,

- 2nd plug at 700' with 50 sx cement,
- 3rd plug at 350' with 25 sx cement,
- 4th plug at 40-0' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement,
- 6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

Signed Steve Durrant (TECHNICIAN)

OCT 15 1990
10-15-90
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
DATE 10-19-90
REV. NO. 29662

EFFECTIVE DATE: 9-19-90

FORM MUST BE TYPED

State of Kansas

20792-0000

FORM MUST BE SIGNED

FORM C-1-6, 90

NOTICE OF INTENTION TO DRILL 033-20,972

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 9 24 1990
month day year

APP NW SE Sec 14 Twp 34 S Rg 20 East West

OPERATOR: License # 3882
Name: Samuel Gary, Jr. & Associates, Inc.
Address: 1775 Sherman Street, Suite 1925
City/State/Zip: Denver, CO 80203
Contact Person: Dan Hall
Phone: 303/831-4673

2080' feet from South line of Section 1980'
feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 7345
Name: Triad Drilling Rig #19

County: Comanche
Lease Name: Lemon Well #: 14-10
Field Name: Lemon Ranch

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): Viola
Nearest lease or unit boundary: 560
Ground Surface Elevation: 1755 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 100 ft.
Depth to bottom of usable water: 220
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 650 ft.
Length of Conductor pipe required: 80 ft.
Projected Total Depth: 6530 ft.
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations: well farm pond X other

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:

AFFIDAVIT

250' RECEIVED
STATE CORPORATION COMMISSION

Exp. 3/14/91

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Joa Weighmaster
SPUD DATE 9-21-90 INIT. A.L.
LENGTH SURFACE PLANNED 650

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 670 CONDUCTOR 62-13
ANHYDRITE T-274 B-6432 ELEVATION

TD 6530 FORMATION Arbuckle well
unconf - water

RAN PIPE @ 500 WOOD-SX Y N
DY TOOL 4759-4886 ALT II DONE

Arbuckle Plug @ 4940 Ft. W/ SX
50' Above below 90 Surface

Hug. Council @ 4700-4940 Ft. W/ SX
Anhydrite Base @ 400 Ft. W/ SD SX

1/2 Base Anhy. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

2 Bottom Surface @ 350 Ft. W/ SD SX

3 40' Plug @ 400 Ft. W/ SD SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Circ. Well) Pond
Hauling

TECHNICIAN SD DATE 10-9-90

TYPE OF CEMENT 60/40 - P2 6% gal.

STARTING TIME 1:00 (AM PM) DATE 10-9-90
COMPLETION TIME 5:00 (AM PM) DATE 10-9-90
CEMENT COMPANY Helliborben
60/40 6% gal.

OCT 15 1990
10-15-90
CONSERVATION DIVISION
Wichita, Kansas