

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- - 033 - 29266<sup>0000</sup>  
SW 1/4 SEC. 5, T 35 S, R 16 W  
990 FEET FROM S SECTION LINE  
990 FEET FROM W SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5171

LEASE NAME Mc Moran WELL # A1

OPERATOR: TX Production Corp  
NAME & ADDRESS 200 W. Douglas, Suite 300  
Wichita, Kansas 67202

COUNTY Comanche  
WELL TOTAL DEPTH 5519 FEET  
CONDUCTOR PIPE: SIZE 4 1/2" FEET 5518  
SURFACE CASING: SIZE 8 5/8 FEET 395

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D&A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Clark Oilfield Services LICENSE NUMBER 5105

ADDRESS 107 W. Fowler, Medicine Lodge Kans 67104

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 31 MONTH: 8 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Elmo Morganstern

(COMPANY NAME) Clark Oilfield Services (PHONE) \_\_\_\_\_

WERE: 1st plug sandbed bottom back to 4940' & dumped 4 bags cement on top of sand. 2nd plug squeezed through 8 5/8" of 4 bag bulls 15 lbs gell + 50 lbs cement + 10 lbs gell & 1 bag bulls released rubber plug & 125 lbs cement. The plugging was accomplished by Sun Cementing w/ 60/40 pop w/ 2% gell & 3% cc.

PLUGGING PROPOSAL RECEIVED BY Paul A. Luthie (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 11:50 AM DAY: 31 MONTH: 8 YEAR: 1983

ACTUAL PLUGGING REPORT This hole was plugged as proposed.

REMARKS: They perforated the 4 1/2" from 5241' to 48' & 4992' to 9.5' they recovered 3000' of 4 1/2" pipe out of this hole. Max pressure 600# shut in @ 400#.

I (DID / DID NOT) OBSERVE THIS PLUGGING.

RECEIVED STATE CORPORATION COMMISSION

SEP 1 1983  
9-1-83  
CONSERVATION DIVISION  
Wichita, Kansas

SIGNED Paul A. Luthie (TECHNICIAN)

INVOICED

DATE 9-15-83  
INV. NO. 5462-W

FORM CP-2/3  
REV. 6-83