

11-6-89

1 051231

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,689-0000
NE NE NE, SEC. 7, T 35 S, R 16 W&E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address 1660 Lincoln Street, Suite 1800
Denver, CO 80264

Lease Name Beeley Well # 1
County Comanche 175.18
Well Total Depth 5390 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 691

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 6 Month: 11 Year: 1989

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 816-886-5606

were: 4 1/2" at 5389' PBSD 5362' Perfs at 5262-66, 5271-77, 5279-86'

1st plug sand back to 5210' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 6 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 5210' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pumped down the 8 5/8" with 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1

sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut-in 50 psi.

Remarks: Used 60/40 Pozmix 2% gel, 3% cc by B.J. Titan. Recovered 4200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
RECEIVED
11-9-89
NOV 9 1989
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE 11-15-89

INV. NO. 26452

Signed Richard W. Judy
(TECHNICIAN)