

To: 1 040429
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-19
API NUMBER 15- 151-21,329 -00-00

NE NW NE, SEC. 19, T 26 S, R 13 W/E

4950 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3517

Lease Name Taylor Well # C-1

Operator: Columbian Resources Corporation

County Pratt 147.10

Name & Address Box 3501

Well Total Depth 4526 feet

Topeka, KS 66601-3501

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 19 Month: 6 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2537

were: 4 1/2" at 4524' PBD 4461' Perfs at 4301-05'

1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9 a.m. Day: 19 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 4 sx cement on top of

sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 200 lbs. hulls and 100 sx cement.

Maximum pressure 275 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1990
CONSERVATION DIVISION
Wichita, Kansas
Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2100' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-3-90

INV. NO. 28534

observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)