

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00001-00-01
Spot: SENW Sec/Twnshp/Rge: 6-35S-36W
1980 feet from N Section Line, 3300 feet from E Section Line
Lease Name: HANKE Well #: 1-6
County: STEVENS Total Vertical Depth: 6861 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4234		WITH 2 SX CMT
II	7.625	2882	2100	WITH 685 SX CMT
PROD	4.5	6849	0	WITH 350 SX CMT
SURF	10.75	700		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/07/2014 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed
Plugging
Method:

SET CIBP @ 4234' WITH 2 SX CMT. RUN CBL & DETERMINE HOW TO PLUG.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 08/07/2014 6:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4234' WITH 2 SX CMT. RUN CBL & FOUND TOC @ 900'. 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG PERFORATE @ 750' WITH 318 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4284	4288		

Received
KANSAS CORPORATION COMMISSION
AUG 20 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

8.27.14 CKM

(TECHNICIAN)

RECEIVED

AUG 15 2014

KCC DODGE CITY