

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20943-00-00  
Spot: SWSW Sec/Twnshp/Rge: 11-33S-35W  
660 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: ALDERMAN Well #: 2-11  
County: STEVENS Total Vertical Depth: 6550 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5870		WITH 2 SX CMT
DVT	5.5	3288		WITH 710 SX CMT
PROD	5.5	6402	1816	WITH 710 SX CMT
SURF	8.625	1790		WITH 850 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2014 3:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5870' WITH 2 SX CMT. PLUG AT 1820' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 07/17/2014 6:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5870' WITH 2 SX CMT. RUN TBG TO 1900' & COULDN'T FIND TOP OF CMT. CUT & PULL CASING AT 1816'. 1ST PLUG AT 1820' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5920	5985		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 20 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
AUG 15 2014  
KCC DODGE CITY

Signed [Signature]  
8-27-14 CKM (TECHNICIAN)

Form CP-2/3