

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20586-00-00  
Spot: E2W2E2W2 Sec/Twnshp/Rge: 30-32S-37W  
2640 feet from S Section Line, 1870 feet from W Section Line  
Lease Name: CRAWFORD Well #: 1-3  
County: STEVENS Total Vertical Depth: 6280 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5960		WITH 2 SX CMT
PROD	5.5	6289	1416	WITH 755 SX CMT
SURF	9.625	1766		WITH 485 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/30/2014 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES Phone: (620) 672-5071

Proposed Plugging Method: EXISTING CIBP @ 5960' WITH 2 SX CMT. PLUG AT 1800' WITH 30 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 06/30/2014 6:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

EXISTING CIBP @ 5960' WITH 2 SX CMT. TOC PER CBL IS 1550'. 1ST PLUG AT 1800' WITH 30 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5678	6083		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 27 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Kenny M Sullivan  
(TECHNICIAN)

8-29-14 CKM

RECEIVED  
AUG 22 2014  
KCC DODGE CITY

Form CP-2/3