

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21253-00-00  
Spot: NENESE Sec/Twnshp/Rge: 8-33S-33W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BRYANT B Well #: 4-8  
County: SEWARD Total Vertical Depth: 6385 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5671		WITH 2 SX CMT
CIBP		5770		WITH 2 SX CMT
PROD	5.5	6156	1573	WITH 390 SX CMT
SURF	8.625	1524		WITH 750 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2014 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5770' WITH 2 SX CMT. SET CIBP @ 5671' WITH 2 SX CMT. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/14/2014 3:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5770' WITH 2 SX CMT. SET CIBP @ 5671' WITH 2 SX CMT. 1ST PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5814	6049		
5721	5754		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 27 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
AUG 22 2014  
KCC DODGE CITY

Signed Kenny Sullivan  
9.2.14 ckm (TECHNICIAN)