

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21841-00-00
Spot: N2S2NW Sec/Twnshp/Rge: 11-14S-15W
3630 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DUMLER C Well #: 14
County: RUSSELL Total Vertical Depth: 3315 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3314		125 SX
SURF	8.625	308		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2014 8:30 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP. Phone: (620) 282-9034

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2014 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations: 1550', 925' and 250'
Ran tubing to 2900' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 1400' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 400' and pumped 75 sx cement w/100 # hulls. Cement circulated out backside. POOH. Hooked to casing and pumped 60 sx cement. Cement circulated out braden head. Shut in and pressured the casing to 350 psi. Shut in.

GPS: 38.85172 -098.96124

Perfs:

Top	Bot	Thru	Comments
3265	3285		
3059	3199		

Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENTING TICKET # 1472

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

9-2-14 CRM

CM

AUG 20 2014