

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21432-00-00
Spot: SWNESWNE Sec/Twnshp/Rge: 10-31S-22W
1880 feet from N Section Line, 1680 feet from E Section Line
Lease Name: GILES RANCH Well #: 3-10
County: CLARK Total Vertical Depth: 6505 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4895		WITH 2 SX CMT
CIBP		5560		WITH 2 SX CMT
CIBP		5642		
PROD	5.5	6491	2260	WITH 375 SX CMT
SURF	8.625	691		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/11/2014 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: CHUCK TONER Company: FALCON EXPLORATION Phone: (620) 546-4752

Proposed Plugging Method: SET CIBP @ 5560' WITH 2 SX CMT. SET CIBP @ 4895' WITH 2 SX CMT. PLUG AT 1190' WITH 15 SX GEL & 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 08/11/2014 7:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5560' WITH 2 SX CMT. SET CIBP @ 4895' WITH 2 SX CMT. PLUG AT 1190' WITH 50 SX GEL & 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5656	5668		
5609	5623		
4945	4950		

Received
KANSAS CORPORATION COMMISSION

AUG 20 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

AUG 12 2014

KCC DODGE CITY

Signed

[Handwritten Signature]
9.2.14 cmm (TECHNICIAN)

SP Form CP-2/3