

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-033-20-266-0000

COUNTY Comanche

McMorran
LEASE NAME _____ WELL# 1

SPOT LOCATION 990 FSL 990 FWL

SEC. 5 TWP. 35 RGE. 16 (X) OR (W)

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

2/3 in file

LEASE OPERATOR Texas Oil & Gas Corp.

PHONE # () (316)-265-9441

OPERATORS LICENSE NO. 5171

CHARACTER OF WELL oil (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 11/29/78 PLUGGING COMMENCED 08/23/83

PLUGGING COMPLETED 08/31/83 REASON FOR ABANDONMENT OF WELL OR PRODUCING
FORMATION- dry

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita, KS

Is ACO-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 5518

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	395	none
				4 1/2	5518	3033

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE
THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO
THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND
DEPTH PLACED, FROM FEET TO FEET EACH SET. Plugged back at 5446 C.I.B.
Pushed plug to 5280. 50 Gallons of sand. Plug moved. Pushed 2nd plug to
5280. 50 gallons of sand. 4 sx. cement o.k. Sun Cementing pumped in
4 hull, 15 jell, 50 cement, 10 jell, 1 hull, drop plug, 125 cement.
60-40 POZ, 2% jell, 3% c.c.

John Clarke & Luthie on location

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Clarke Corp. LICENSE No. 5105
ADDRESS P.O. Box 187 / Medicine Lodge, KS / 67104

STATE OF _____ COUNTY OF _____, SS.

(EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT. SO HELP ME GOD.

(SIGNATURE) *John Clarke*
(ADDRESS) _____

SUBSCRIBED AND SWORN TO BEFORE ME THIS 8 DAY OF September, 1983

Lamela Ricks
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

MY COMMISSION EXPIRES: 9-27-83

SEP - 8 1983
9-8-83
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 5 T. 35S R. 16W
LOC. 990' FSL & 990' FWL

FARM McMoran "A" NO. 1

COUNTY Comanche

ROTARY TOTAL DEPTH 5,519'
COMM. October 13, 1978 COMP. October 29, 1978
CONTRACTOR H-30, Inc. (Rig #77)
ISSUED November 3, 1978

CASINO

10 3/4"
8 5/8" Set at 395' cemented w/350. sxs cement
5 1/2"
4 1/2" Set at 5,518' cemented w/225 sxs cement

ELEVATION 1,854' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	715'
Shale and Lime	1,000'
Red Bed and Shale	1,405'
Lime and Shale	2,070'
Shale and Lime	2,224'
Shale and Anhydrite	2,405'
Lime and Shale	3,366'
Shale and Lime	3,566'
Lime and Shale	4,800'
Lime	5,031'
Lime and Shale	5,138'
Lime	5,176'
Lime and Shale	5,223'
Lime	5,308'
Lime and Chert	5,519'
Rotary Total Depth	5,519'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting

Dean Britting

State of Kansas)
County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd day of November, 1978.

Elsie Willison

Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

AUG 18 1983

8-18-83

Wichita, Kansas

PROD. FILE