

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County, Sec. 17 Twp. 26 Rge. 13 NE (W) (W)

Location as "NE/CNW/SW" or footage from lines CN NE/4 NE/4 SW/4

Lease Owner Transit Corporation

Lease Name Parker Well No. 1

Office Address 1516 Liberty Bank Bldg., Okla. City 1, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 11-28 19 55

Application for plugging filed 11-28 19 55

Application for plugging approved 11-28 19 55


Plugging commenced 11-28 19 55

Plugging completed 11-28 19 55

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	846'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 300 ft. with heavy drilling mud, set plug and cemented with 20 sacks cement. Filled hole to 35 ft. with heavy drilling mud, set plug and cemented to bottom of cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation

Address 1516 Liberty Bank Bldg., Okla. City, Okla.

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

C. W. Dodson (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 55

My commission expires Jan. 28, 1959

Jane A. Brady Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 3 - 1955

CONSERVATION DIVISION

PLUGGING  
FILE SEC 17 T 26 R 13W  
BOOK PAGE 20 LINE 22

TRANSIT CORPORATION  
 Parker #1 - Sec. 17-26S-13W  
 Pratt County, Kansas.  
 Driller's Log

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay & Shale	0	90
Shale & Shells	90	300
Shale & Sand	300	510
Shale & Shells	510	824
Anhydrite	824	838
Anhydrite & Red Bed	838	1192
Lime & Shale	1192	1910
Lime	1910	2105
Lime	2105	2245
Shale	2245	2315
Lime	2315	2470
Shale	2470	2575
Lime	2575	2589
Lime & Shale	2589	2880
Lime	2880	2954
Shale & Lime	2954	3565
Lime	3565	3615
Shale & Lime	3615	3818
Lime	3818	4124
Shaley Lime	4124	4144
Lime	4144	4206
Shale & Lime	4206	4241
Lime	4241	4280
Lime & Shale	4280	4330
Lime & Chert	4330	4344
Shale & Lime Chert	4344	4370
Lime & Chert	4370	4426
Lime	4426	4437
Lime & Dolomite	4437	4460
Simpson Sand	4460	4462
Simpson Shale	4462	4499
Shale	4499	4511
Arbuckle	4511	4528
Lime	4528	4545

838' of 8-5/8" surface csg. cemented w/ 500 sx. cement.

T.D.

<u>Electric Log Tops</u>	
Heebner	3637
Brown Lime	3789
Lansing	3813
Base K. C.	4126
Mississippi	4256
Kinderhook Shale	4305
Viola	4382
Simpson Shale	4430
Simpson Dolomite	4438
Arbuckle	4516

I hereby certify the foregoing to be a true and accurate Driller's Log of the formations encountered in the above well.

TRANSIT CORPORATION

BY *C. Hodson*

Subscribed and sworn to before me this 1st day of December, 1955.

My commission expires Jan. 28, 1959.

*Jane A. Brady*  
 Notary Public, State of Oklahoma.

**PLUGGING**  
 FILE SEC 17-26S-13W  
 BOOK PAGE 20 LINE 22

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 DEC 3 - 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas