


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County. Sec. 10 Twp. 26 Rge. 13 (X) (W)
Location as "NE/CNW%SW%" or footage from lines NW SE SW
Lease Owner Petroleum, Inc.
Lease Name HEISEL Well No. 1
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 19, 19 53
Application for plugging filed November 19, 19 53
Application for plugging approved November 19, 19 53
Plugging commenced November 19, 19 53
Plugging completed November 19, 19 53
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 255' and set wooden plug
at 255'. Placed 1/2 sack hulls on top
of plug at 255'. Cemented and displaced
through drill pipe 20 sacks cement onto
plug and hulls at 255'. Mudded up to
40' and set second wooden plug at 40'.
Filled hole to bottom of well cellar
with 10 sacks cement.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
W.W. Fisher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.W. Fisher
305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of November, 19 53
Charlotte Meisner
Notary Public.

My commission expires October 13, 1954



DRILLER'S LOG HELSEL #1

Petroleum, Inc., Operator

Section 10, Twp. 26S, Rge. 13W

Garvey Drilling Company, Contractor

Location: NW SE SW

Drilling Commenced: November 4, 1953

County: Pratt County, Kansas

Drilling Completed: November 19, 1953

Production: D & A

Casing Record: 8 5/8" @ 255' w/225 sax

R.T.D.: 4393'

Figures below indicate bottom of formations:

		<u>Tops</u>
40	Sand & Coarse Rock	
175	Coarse Sand	
780	Red Bed	Heobner: 3553 (-1626)
807	Anhydrite	Brown Lime: 3716 (-1789)
1800	Shale & Shells	Lansing: 3745 (-1818)
3758	Lime & Shale	Viola: 4204 (-2277)
4177	Lime	Simpson: 4297 (-2370)
4177	Chert	Arbuckle: 4360 (-2433)
4207	Cherty Lime	
4291	Chert	
4303	Cherty Shale	
4343	Shale	
4367	Lime & Shale	
4393	Lime	
4393	R.T.D.	

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fish

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 23rd day of November, 1953.

Charice Jones
Notary Public

My commission expires: October 13, 1954

PLUGGING	
FILE	SEC <u>10</u> T <u>26</u> R <u>13W</u>
BOOK	PAGE <u>144</u> LINE <u>20</u>