


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, Sec. 28 Twp. 26 Rge. 13 ~~XXX~~ (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE NW
Lease Owner Sunray Mid-Continent Oil Company
Lease Name L. E. Frisbie Well No. 1
Office Address Box 195, GreatBend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 10-27 19 51
Application for plugging filed 10-28 19 55
Application for plugging approved 10-29 19 55
Plugging commenced 12-2 19 55
Plugging completed 12-9 19 55
Reason for abandonment of well or producing formation Reached economic limit of production.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well S. S. Grieder
Producing formation Viola Lime Depth to top 4314 1/2 Bottom 4355 Total Depth of Well 4427 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---|---------|------|------|--------|--------|------------|
| Lensing-Kc | none | 3790 | 4003 | 13" | 267' | 0 |
| Viola Lime | Oil | 4267 | 4360 | 8 5/8" | 914' | 0 |
| Arbuckle Lime | Water | 4444 | 4476 | 5 1/2" | 4475 | 3373' |
| Hole was plugged back to 4429', perf. 4314-4324'. | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 4429-4300' and pumped 5 sacks cement. Pulled casing up to 1700 and spotted, 30 sacks gel used. Mudded the hole to 300'. Set 10' rock bridge and ran 20 sacks of cement on top of bridge. Mudded the hole to 35', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company, Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Allen N. Thomas, (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allen N. Thomas

Box 195, GreatBend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 1955

My commission expires December 24, 1956

Notary Public.

PLUGGING
FILED SEC 28 T 26 R 13W
NOOK PAGE 20 LINE 2

DE. 15 1955
CONSERVATION DIVISION
Wichita, Kansas

Tulsa, Oklahoma
October 19, 1951

Sunray Oil Corporation
Tulsa, Oklahoma

STICKLE DRILLING COMPANY: CONTRACTOR

L.E. Frisbee #1
SE SE NW Sec. 28-268-13W
Pratt County, Kansas

Drilling commenced: 9-14-51
Drilling completed 10-15-51

DRILLERS LOG

| | |
|----------------------|--------------------------|
| Sand | 0-220 |
| Red Bed | 220-270 |
| Shale & Shells | 270-410 |
| Red Bed | 410-792 |
| Red Bed & Shells | 792-885 |
| Red Bed | 885-890 |
| Anhydrite | 890-912 |
| Red Bed | 912-915 |
| Red Rock & Shale | 915-1225 |
| Shale & Shells | 1225-1420 |
| Salt & Shells | 1420-1610 |
| Shale & Shells | 1610-1870 |
| Lime & Shale | 1870-1945 |
| Lime | 1945-2455 |
| Lime & Shale | 2455-2675 |
| Shale & Lime | 2675-2760 |
| Lime & Shale | 2760-2950 |
| Shale & Lime | 2950-3035 |
| Lime & Shale | 3035-3235 |
| Lime | 3235-3240 |
| Lime & Shale | 3240-3325 |
| Lime | 3325-3610 |
| Lime & Shale | 3610-3710 |
| Lime | 3710-4075 |
| Lime & Shale | 4075-4113 |
| Lime | 4113-4175 |
| Lime Chert | 4175-4215 |
| Cherty Lime & Shale | 4215-4251 |
| Shale & Chert | 4251-4280 |
| Viola | 4280-4303 |
| Chert & Shale | 4303-4335 |
| Shale & Chert | 4335-4373 |
| Lime & Shale | 4373-4392 |
| Simpson Sand & Shale | 4392-4427 |
| Shale, Sand & Lime | 4427-4448 |
| Arbuckle Chert | 4448-4477 TD with rotary |


I, Frank E. Stickle, hereby certify the above to be a true and complete drillers log of The Sunray Oil Corporation's L.E. Frisbee #1 SE SE NW Section 28-268-13W, Pratt County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

My commission expires:

February 13, 1952



DEPARTMENT OF COMMERCE
Wilmington, Delaware